

FRAMING JUST GOT FASTER, EASIER,  
AND MORE PROFITABLE.

# WELCOME TO NEXTPHASE JOBPACK



POWERED BY

**NextPhase®**  
SITE SOLUTIONS



Weyerhaeuser

# NEXTPHASE SITE SOLUTIONS

FROM WEYERHAEUSER



What's it worth to shave a few days off the schedule? What's the cost of a callback? If you know, then you understand how critical it is to have the right framing materials on site when you need them, ready to assemble.

NextPhase® Site Solutions improves framing efficiency by combining proven Trus Joist® products with proprietary software and computerized saw technology into precision-cut JobPack® framing packages. These floor, wall or roof framing packages:

- Make framing faster and easier, reducing labor costs that saves you and the homeowner money
- Provide pre-cut components in bundles that match framing layouts
- Reduce waste, human error and product damage by eliminating job site cutting
- Help you build a quality home in less time




# NEXTPHASE JOBPACK FRAMING

BETTER FRAMING BY DESIGN

**DRAW**



**OPTIMIZE**



**CUT**



**DELIVER**



# MAKE THE CALL

AND YOU'RE ON YOUR WAY TO BETTER FRAMING

NextPhase JobPack framing will transform your framing process into a simpler, more cost-efficient routine.

**For more information  
about NextPhase®  
JobPack® framing,  
contact your local  
Weyerhaeuser dealer  
or call 888-453-8358.**

POWERED BY

**NextPhase®**  
SITE SOLUTIONS





# NEXTPHASE JOBPACK FRAMING

Consider the value you'll see by framing faster and better, delivering more houses in less time with confidence and consistency. Now you're ready for NextPhase® Jobpack Framing.

JOBPACK FRAMING PROVIDES:	YOUR BENEFIT:
Readily available, superior-quality TJI® joists, beams, panels, and accessories.	An integrated structural floor system ready to deliver on time to the job site.
Detailed floor framing layouts and bundled products to your specification.	The ability to stage materials on the job site for faster assembly.
All materials are identified by label and are marked for blocking, connectors, mechanical rough-ins, and intersecting members.	Instant reference from the placement plans for fast and accurate assembly that reduces cycle time and labor costs.
Materials accurately pre-cut to length.	Minimize field measuring and trimming—products drop into place for faster, safer installation.
Framing members pre-drilled for mechanical rough-ins.	Fewer mis-cuts, damaged materials, and delays, reducing hard costs

**Ask your Weyerhaeuser dealer how to get started today.**



[woodbywy.com](http://woodbywy.com)

**888.453.8358**

**POWERED BY**

**NextPhase®**  
SITE SOLUTIONS

▲ Weyerhaeuser, JobPack, NextPhase, TJI and Trus Joist are registered trademarks of Weyerhaeuser NR.  
© 2013 Weyerhaeuser NR Company. All rights reserved.

SVC-7002 5/13

